## OPERATION AND MAINTENANCE GUIDES



O&M For:	EI1025000	
Date:	November 2023	
Code:	El1025000	
Description:	ENDURO Industrial Tank 25,000 Ltr - North Island	
Product Warranty:	1 year	

SPECIFICATIONS						
	Capacity (L)	Diameter (mm)	Height (mm)	Outlets	Manhole Dia (mm)	
	25,000	3675	2770	2 x50	610	
Standard	• AS/NZS 2070 (	Complies with:  • AS/NZS 4020: Products in contact with drinking water  • AS/NZS 2070 (INT): Plastics material for food contact use  • Certified to AS/NZS 4766:2006: Water & Chemical Tank Standard				
Uses	<ul><li>Potable Water Storage</li><li>Retention/Detention Stormwater Management</li><li>Industrial Applications</li></ul>					
Statement	-	s focus on Ecologically is committed to supply			ng Initiatives and 5 Star g Solutions.	

## **MAINTENANCE**

Description	Action	Frequency
Tank Stability	Tank must remain level, foundation must not become eroded	Monthly
Tank Lid	Remains securely fitted	Bi-Monthly
Inlet/Outlet Fitting	Remains securely fitted with no leakage	Bi-Monthly
Pump	Check Pump, if fitted, for inlet screen blockages	Bi-Monthly
Sediment Build Up	Remains lower than base outlet - if outlet flow becomes restricted remove sediment with vacuum truck. Re-attach tank lid securely.	Half yearly or as necessary

Promax Plastics confirms that if these tanks are installed according to Good Management practices set out in the Promax Installation Guides, they will perform as stated throughout their intended life.

Please note: Entry into this tank is at owners risk.

## **OPERATION AND MAINTENANCE GUIDES**



Responsibility: The owner/s are responsible for maintenance of the tank.

**Post Storm** Inspection: Following a storm event it is recommended that a full tank inspection is carried out, please refer

the maintenance section for guidelines on this.

**Debris removal** programme:

If debris is identified in either a regular maintenance check or post storm inspection it is recommended that this is removed by a professional stormwater maintenance provider.

## MAINTENANCE RECORDS

Date	Comments	Completed